

Best Available Copy



PCT/AU03/01117

REC'D 30 SEP 2003

WIPO

PCT


Patent Office
Canberra

I, LISA TREVERROW, MANAGER OF THE AUSTRALIAN RECEIVING OFFICE, hereby certify that the annexed is a true copy of International Application PCT/AU02/01762 filed at the Australian Receiving Office on 23 December 2002.

I further certify that this International Application claims priority from Provisional Application PR9673 filed on 21 December 2001.

**PRIORITY
DOCUMENT**

SUBMITTED OR TRANSMITTED IN
COMPLIANCE WITH RULE 17.1(a) OR (b)



WITNESS my hand this
Twenty second day of September 2003

Lisa Treverrow

LISA TREVERROW
MANAGER
AUSTRALIAN RECEIVING OFFICE

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

PCT/AU 02/01762
International Application No.

23 DEC 2002 (23/12/02)
International Filing Date

Australian Patent Office
Name of Receiving Office and PCT International Application

Applicant's or agent's file reference
(if desired) (12 characters maximum)

34148WOP00

Box No. I TITLE OF INVENTION
A CONTROL CIRCUIT

Box No. II APPLICANT ☐ This person is also inventor

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

Energy Storage Systems Pty Ltd
Units 9 & 10, 12 Mars Road
Lane Cove, New South Wales 2066
Australia

Telephone No. (612) 9490 5315

Facsimile No. (612) 9490 5311

Teleprinter No.

Applicant's registration No. with the Office

State (that is, country) of nationality: AU

State (that is, country) of residence: AU

This person is applicant for the purposes of: ☐ all designated States ☒ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

TURNER, Geoff
Units 9 & 10
12 Mars Road
Lane Cove, New South Wales 2066
Australia

This person is

☐ applicant only

☒ applicant and inventor

☐ inventor only (If this check-box is marked, do not fill in below)

Applicant's registration No. with the Office

State (that is, country) of nationality: AU

State (that is, country) of residence: AU

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

☒ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:

☒ agent ☐ common representative

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country)

BALDWIN SHELSTON WATERS
60 Margaret Street
Sydney NSW 2000
AUSTRALIA

Telephone No. (02) 9777 1111

Facsimile No. (02) 9241 4666

Teleprinter No.

Agent's registration No. with the Office

☐ Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Continuation of Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)*If none of the following sub-boxes is used, this sheet should not be included in the request.*

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

SMITH, Trevor
Units 9 & 10
12 Mars Road
Lane Cove, NSW 2066
Australia

This person is

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below)

Applicant's registration No. with the Office

State (that is, country) of nationality: AU

State (that is, country) of residence: AU

This person is applicant for the purposes of:

- ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)

This person is

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below)

Applicant's registration No. with the Office

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of:

- ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)

This person is

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below)

Applicant's registration No. with the Office

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of:

- ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)

This person is

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below)

Applicant's registration No. with the Office

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of:

- ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No.V DESIGNATION OF STATES

Mark the applicable check-boxes below; at least one must be marked.

The following designations are hereby made under Rule 4.9(a):

Regional Patent

- ☒ AP ARIPO Patent: GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, MZ Mozambique, SD Sudan, SL Sierra Leone, SZ Swaziland, TZ United Republic of Tanzania, UG Uganda, ZM Zambia, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT (if other kind of protection or treatment desired, specify on dotted line:)
- ☒ EA Eurasian Patent: AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ EP European Patent: AT Austria, BE Belgium, BG Bulgaria, CH and LI Switzerland and Liechtenstein, CY Cyprus, CZ Czech Republic, DE Germany, DK Denmark, EE Estonia, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, SI Slovenia, SK Slovakia, TR Turkey, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☒ OA OAPI Patent: BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GQ Equatorial Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line):

National Patent (if other kind of protection or treatment desired, specify on dotted line)

- | | | |
|---|--|--|
| <input checked="" type="checkbox"/> AE United Arab Emirates | <input checked="" type="checkbox"/> GE Georgia | <input checked="" type="checkbox"/> MX Mexico |
| <input checked="" type="checkbox"/> AG Antigua and Barbuda | <input checked="" type="checkbox"/> GH Ghana | <input checked="" type="checkbox"/> MZ Mozambique |
| <input checked="" type="checkbox"/> AL Albania | <input checked="" type="checkbox"/> GM Gambia | <input checked="" type="checkbox"/> NO Norway |
| <input checked="" type="checkbox"/> AM Armenia | <input checked="" type="checkbox"/> HR Croatia | <input checked="" type="checkbox"/> NZ New Zealand |
| <input checked="" type="checkbox"/> AT Austria | <input checked="" type="checkbox"/> HU Hungary | <input checked="" type="checkbox"/> OM Oman |
| <input checked="" type="checkbox"/> AU Australia | <input checked="" type="checkbox"/> ID Indonesia | <input checked="" type="checkbox"/> PH Philippines |
| <input checked="" type="checkbox"/> AZ Azerbaijan | <input checked="" type="checkbox"/> IL Israel | <input checked="" type="checkbox"/> PL Poland |
| <input checked="" type="checkbox"/> BA Bosnia and Herzegovina | <input checked="" type="checkbox"/> IN India | <input checked="" type="checkbox"/> PT Portugal |
| | <input checked="" type="checkbox"/> IS Iceland | <input checked="" type="checkbox"/> RO Romania |
| <input checked="" type="checkbox"/> BB Barbados | <input checked="" type="checkbox"/> JP Japan | <input checked="" type="checkbox"/> RU Russian Federation |
| <input checked="" type="checkbox"/> BG Bulgaria | <input checked="" type="checkbox"/> KE Kenya | <input checked="" type="checkbox"/> SD Sudan |
| <input checked="" type="checkbox"/> BR Brazil | <input checked="" type="checkbox"/> KG Kyrgyzstan | <input checked="" type="checkbox"/> SE Sweden |
| <input checked="" type="checkbox"/> BY Belarus | <input checked="" type="checkbox"/> KP Democratic People's Republic Of Korea | <input checked="" type="checkbox"/> SG Singapore |
| <input checked="" type="checkbox"/> BZ Belize | | <input checked="" type="checkbox"/> SI Slovenia |
| <input checked="" type="checkbox"/> CA Canada | <input checked="" type="checkbox"/> KR Republic of Korea | <input checked="" type="checkbox"/> SK Slovakia |
| <input checked="" type="checkbox"/> CH & LI Switzerland and Liechtenstein | <input checked="" type="checkbox"/> KZ Kazakhstan | <input checked="" type="checkbox"/> SL Sierra Leone |
| <input checked="" type="checkbox"/> CN China | <input checked="" type="checkbox"/> LC Saint Lucia | <input checked="" type="checkbox"/> TJ Tajikistan |
| <input checked="" type="checkbox"/> CO Colombia | <input checked="" type="checkbox"/> LK Sri Lanka | <input checked="" type="checkbox"/> TM Turkmenistan |
| <input checked="" type="checkbox"/> CR Costa Rica | <input checked="" type="checkbox"/> LR Liberia | <input checked="" type="checkbox"/> TN Tunisia |
| <input checked="" type="checkbox"/> CU Cuba | <input checked="" type="checkbox"/> LS Lesotho | <input checked="" type="checkbox"/> TR Turkey |
| <input checked="" type="checkbox"/> CZ Czech Republic | <input checked="" type="checkbox"/> LT Lithuania | <input checked="" type="checkbox"/> TT Trinidad and Tobago |
| <input checked="" type="checkbox"/> DE Germany | <input checked="" type="checkbox"/> LU Luxembourg | <input checked="" type="checkbox"/> TZ United Republic of Tanzania |
| <input checked="" type="checkbox"/> DK Denmark | <input checked="" type="checkbox"/> LV Latvia | <input checked="" type="checkbox"/> UA Ukraine |
| <input checked="" type="checkbox"/> DM Dominica | <input checked="" type="checkbox"/> MA Morocco | <input checked="" type="checkbox"/> UG Uganda |
| <input checked="" type="checkbox"/> DZ Algeria | <input checked="" type="checkbox"/> MD Republic of Moldova | <input checked="" type="checkbox"/> US United States of America |
| <input checked="" type="checkbox"/> EC Ecuador | | <input checked="" type="checkbox"/> UZ Uzbekistan |
| <input checked="" type="checkbox"/> EE Estonia | <input checked="" type="checkbox"/> MG Madagascar | <input checked="" type="checkbox"/> VN Viet Nam |
| <input checked="" type="checkbox"/> ES Spain | <input checked="" type="checkbox"/> MK The former Yugoslav Republic of Macedonia | <input checked="" type="checkbox"/> YU Yugoslavia |
| <input checked="" type="checkbox"/> FI Finland | <input checked="" type="checkbox"/> MN Mongolia | <input checked="" type="checkbox"/> ZA South Africa |
| <input checked="" type="checkbox"/> GB United Kingdom | <input checked="" type="checkbox"/> MW Malawi | <input checked="" type="checkbox"/> ZM Zambia |
| <input checked="" type="checkbox"/> GD Grenada | | <input checked="" type="checkbox"/> ZW Zimbabwe |

Check-boxes below reserved for designating States which have become party to the PCT after issuance of this sheet:

- ☒ VC St Vincent and the Grenadines ☐ We wish to designate all possible States ☐
- ☒ SC Seychelles ☐

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation (including fees) must reach the receiving Office within the 15-month time limit).

PCT/AU 02 / 01762

Box No. VI PRIORITY CLAIM

The priority of the following earlier application(s) is hereby claimed:

Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		National application: country	regional application:* regional Office	international application receiving Office
Item (1) 21 December 2001 (21.12.01)	PR9673	AU		
Item (2)				
Item (3)				
Item (4)				
Item (5)				

☐ Further priority claims are indicated in the Supplemental Box.

The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of this international application is the receiving Office) identified above as:

☐ all items
 ☒ item (1)
 ☐ item (2)
 ☐ item (3)
 ☐ item (4)
 ☐ item (5)
 ☐ other, see Supplemental Box

*Where the earlier application is an ARIPO application, indicate at least one country party to the Paris Convention for the Protection of Industrial Property one Member of the World Trade Organization for which that earlier application was filed (Rule 4.10(b)(ii)).

Box No. VII INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA) (if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):

ISA /

Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):

Date (day/month/year) Number Country (or regional Office)

Box No. VIII DECLARATIONS

The following declarations are contained in Boxes Nos. VIII (i) to (v) (mark the applicable Check-boxes below and indicate in the right column the number of each type of declaration):

Number of
Declarations


- | | | | |
|--------------------------|--------------------|--|---|
| <input type="checkbox"/> | Box No. VIII (i) | Declaration as to the identity of the inventor | : |
| <input type="checkbox"/> | Box No. VIII (ii) | Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent | : |
| <input type="checkbox"/> | Box No. VIII (iii) | Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application | : |
| <input type="checkbox"/> | Box No. VIII (iv) | Declaration of inventorship (only for the purposes of the designation of the United States of America) | : |
| <input type="checkbox"/> | Box No. VIII (v) | Declaration as to non-prejudicial disclosures or exceptions to lack of novelty | : |

Box No. IX CHECK LIST; LANGUAGE OF FILING

This international application contains:		This international application is accompanied by the following item(s) (mark the applicable check-boxes below and indicate in right column the number of each item):		Number of item
(a) the following number of sheets in the paper form:				
request (including declaration sheets)	5	1. <input checked="" type="checkbox"/> fee calculation sheet	:	
description (excluding sequence listing part)	15	2. <input type="checkbox"/> original separate power of attorney	:	
claims	3	3. <input type="checkbox"/> original general power of attorney:	:	
abstract	1	4. <input type="checkbox"/> copy of general power of attorney; reference number; if any:	:	
drawings	3	5. <input type="checkbox"/> statement explaining lack of signature	:	
Sub-total number of sheets	27	6. <input type="checkbox"/> priority document(s) identified in Box No. VI as item(s);	:	
sequence listing part of description (actual number of sheets if filed in paper form, whether or not also filed in computer readable form; see (b) below)	0	7. <input type="checkbox"/> translation of international application into (language);	:	
Total number of sheets	27	8. <input type="checkbox"/> separate indications concerning deposited microorganism or other biological material	:	
(b) sequence listing part of description filed in computer readable form		9. sequence listing in computer readable form (indicate also type and number of carriers) (diskette, CD-ROM, CD-R or other):		
(i) <input type="checkbox"/> only (under Section 801(a)(i))		(i) <input type="checkbox"/> copy submitted for the purposes of international search under Rule 13ter only (and not as part of the international application)	:	
(ii) <input type="checkbox"/> in addition to being filed in paper form (under Section 801(a)(ii))		(ii) <input type="checkbox"/> (only where check-box (b)(i) or (b)(ii) is marked in left column) additional copies including, where applicable, the copy for the purposes of international search under Rule 13ter	:	
Type and number of carriers (diskette, CD-ROM, CD-R or other) on which the sequence listing part is contained (additional copies to be indicated under item 9(ii), in right column):		(iii) <input type="checkbox"/> together with relevant statement as to the identity of the copy or copies with the sequence listing part mentioned in left column	:	
Figure of the drawings which should accompany the abstract:	Fig. 1	10. <input type="checkbox"/> other (specify):	:	
Language of filing of the international application:		ENGLISH		

Box No. X SIGNATURE OF APPLICANT, AGENT OR COMMON REPRESENTATIVE

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).


 John B. Redfern
 BALDWIN SHELSTON WATERS

For receiving Office use only		For International Bureau use only	
1. Date of actual receipt of the purported international application:	23 DEC 2002 (23/12/02)	2. Drawings:	<input checked="" type="checkbox"/> received:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:			<input type="checkbox"/> not received:
4. Date of timely receipt of the required corrections under PCT Article 11(2):		5. International Searching Authority (if two or more are competent):	ISA/
6. <input type="checkbox"/> Transmittal of search copy delayed until search fee if paid			

Date of receipt of the record copy by International Bureau:

- 1 -

TITLE: A CONTROL CIRCUIT FOR A LOAD

FIELD OF THE INVENTION

The present invention relates to a control circuit and in particular to a control circuit for a load.

5 The invention has been developed primarily for a laptop computer that makes use of a variety of power/energy sources and will be described hereinafter with reference to that application. It will be appreciated, however, that the invention is not limited to that particular field of use and is also applicable to other portable computing devices, portable electronic devices, wireless devices, or those devices drawing power/energy from multiple
10 and distinct storage elements or sources.

BACKGROUND TO THE INVENTION

With the increasing demand for portable computing devices and portable wireless computing devices, there has been considerable effort expended in the development of portable power supplies for such devices. The usual approach is to rely upon a battery
15 pack that is periodically recharged from the mains supply. The battery pack typically includes a plurality of interlinked batteries in combination with protection circuitry to prevent the current provided by the batteries from exceeding a predetermined maximum operational current. If that maximum is exceeded, the protection circuitry isolates the batteries from the computing device. In some cases the circuitry also, after a delay,
20 reconnects the batteries. In any case, the step of isolating the batteries from the device is that the device shuts down. Clearly, this is inconvenient to the user.

The load current drawn by computing devices varies greatly, and sharply, with time. This creates enormous voltage ripple for the battery pack. This, in turn, is not ideal for most batteries, many of which are best suited to provide steady current levels.
25 Moreover, the peak load currents are often large in comparison to the average load current, although only of short duration. This requires that additional complexity be designed into the protection circuit to prevent undesirable triggering of that circuit.

There has been some evidence of the proposed use of supercapacitors to supply power to portable electronic devices, although as a source secondary to the battery pack.
30 Such devices are usually accompanied by a second protection circuit to limit the flow of current to and from the supercapacitor. This circuitry tends to significantly degrade the effectiveness of the supercapacitor in these applications.

- 1 -

TITLE: A CONTROL CIRCUIT

FIELD OF THE INVENTION

The present invention relates to a control circuit and in particular to a control circuit for a load.

5 The invention has been developed primarily for a laptop computer that makes use of a variety of power/energy sources and will be described hereinafter with reference to that application. It will be appreciated, however, that the invention is not limited to that particular field of use and is also applicable to other portable computing devices, portable electronic devices, wireless devices, or those devices drawing power/energy from multiple
10 and distinct storage elements or sources.

BACKGROUND TO THE INVENTION

With the increasing demand for portable computing devices and portable wireless computing devices, there has been considerable effort expended in the development of portable power supplies for such devices. The usual approach is to rely upon a battery
15 pack that is periodically recharged from the mains supply. The battery pack typically includes a plurality of interlinked batteries in combination with protection circuitry to prevent the current provided by the batteries from exceeding a predetermined maximum operational current. If that maximum is exceeded, the protection circuitry isolates the batteries from the computing device. In some cases the circuitry also, after a delay,
20 reconnects the batteries. In any case, the step of isolating the batteries from the device is that the device shuts down. Clearly, this is inconvenient to the user.

The load current drawn by computing devices varies greatly, and sharply, with time. This creates enormous voltage ripple for the battery pack. This, in turn, is not ideal for most batteries, many of which are best suited to provide steady current levels.
25 Moreover, the peak load currents are often large in comparison to the average load current, although only of short duration. This requires that additional complexity be designed into the protection circuit to prevent undesirable triggering of that circuit.

There has been some evidence of the proposed use of supercapacitors to supply power to portable electronic devices, although as a source secondary to the battery pack.
30 Such devices are usually accompanied by a second protection circuit to limit the flow of current to and from the supercapacitor. This circuitry tends to significantly degrade the effectiveness of the supercapacitor in these applications.

- 2 -

Any discussion of the prior art throughout the specification should in no way be considered as an admission that such prior art is widely known or forms part of common general knowledge in the field.

DISCLOSURE OF THE INVENTION

5 It is an object of the present invention, at least in the preferred embodiment, to overcome or ameliorate one or more of the disadvantages of the prior art, or to provide a useful alternative.

According to a first aspect of the invention there is provided a control circuit for a load, the circuit including:

10 input terminals for electrically connecting with respective terminals of a battery that has a predetermined maximum operational current whereby the battery supplies a battery current;

output terminals for electrically connecting in parallel the load and a supercapacitor; and

15 a controller being disposed between the input and the output terminals for allowing the battery to transfer energy to the load and the supercapacitor while maintaining the battery current at less than the predetermined maximum operational current.

Preferably, the controller also prevents the supercapacitor from providing energy to the battery. More preferably, the circuit is a power-up protection circuit for a portable
20 computing device.

Preferably also, the load draws a load current that varies with time, where the load current is the sum of the battery current and the current provided by the supercapacitor. More preferably, the load current is greater than or equal to zero and the controller maintains the battery current at greater or equal to zero. In other embodiments, the battery
25 current is allowed to be negative, but only for small magnitude currents and for short periods of time.

In a preferred form, the predetermined maximum operational current is an average over a given interval. However, in other embodiments it is an instantaneous current.

Preferably also, the battery includes a plurality of battery cells. More preferably,
30 the battery includes a protection circuit for electrically disconnecting the battery terminals from the input terminals in response to the predetermined maximum operation current being exceeded.

- 3 -

Preferably, the controller is responsive to the battery current for varying a resistance between the input and the output terminals. More preferably, the controller includes one or more solid-state devices for varying the resistance. Even more preferably, at least one of the solid-state devices is a MOSFET.

- 5 Preferably also, the load has a start up sequence and the at least one of the solid-state devices operates in a linear mode during that sequence. More preferably, the at least one solid state device is mounted to a heat sink.

According to a second aspect of the invention there is provided a control circuit for a load, the circuit including:

- 10 input terminals for electrically connecting with respective terminals of a battery that has a predetermined maximum operational current whereby the battery supplies a battery current;

 output terminals for electrically connecting in parallel the load and a supercapacitor; and

- 15 a solid state device through which the battery current flows between the input and the output terminals, the transistor being responsive to the battery current for varying the resistance of the transistor and thereby allowing the battery to transfer energy to the load while maintaining the battery current at less than the predetermined maximum operational current.

- 20 Preferably, the solid state device is a transistor, and more preferably a MOSFET. Even more preferably, the MOSFET is mounted to a heat sink.

According to a third aspect of the invention there is provided a control circuit for a computing device that derives power from a battery unit that has a battery and a protection circuit for isolating the battery from the device when predetermined maximum operational
25 current is exceeded, the control circuit including:

 input terminals for electrically connecting with respective terminals of the protection circuit to allow the battery to supply a battery current to the device;

 output terminals for electrically connecting in parallel the load and a supercapacitor; and

- 30 a controller being disposed between the input and the output terminals for allowing the battery to transfer energy to the load and the supercapacitor while maintaining the battery current at less than the predetermined maximum operational current.

- 4 -

According to a fourth aspect of the invention there is provided a portable computing device including:

- a power source having at least two output terminals for supplying a source current of up to a predetermined maximum operational current;
- 5 computer hardware that includes a supply rail that draws a load current;
- a supercapacitor in parallel with the supply rail; and
- a controller being disposed between the output terminals and the supply rail for allowing the source to transfer energy to the hardware and the supercapacitor while maintaining the source current at less than the predetermined maximum operational
- 10 current.

According to a fifth aspect of the invention there is provided a control circuit for a load, the circuit including:

- input terminals for electrically connecting with respective terminals of a battery that supplies a battery current, wherein the battery has a predetermined maximum
- 15 operational current and a predetermined pulse current capacity;
- output terminals for electrically connecting in parallel the load and a supercapacitor; and
- a controller being disposed between the input and the output terminals for allowing the battery to transfer energy to the load and the supercapacitor while controlling the
- 20 battery current such that the battery remains within the predetermined pulse current capacity.

- Preferably, the controller provides a current path for the battery current between the input and the output terminals and is responsive to both the quantum and the duration of the battery current for varying the resistance of the path. More preferably, the
- 25 resistance of the path is varied once the predetermined pulse current capacitor has been reached. Even more preferably, the resistance of the path is varied to maintain battery current below the predetermined maximum operation current.

BRIEF DESCRIPTION OF THE DRAWING

- A preferred embodiment of the invention will now be described, by way of
- 30 example only, with reference to the accompanying drawings in which:

Figure 1 is a block diagram of a portable computing device according to the invention;

- 5 -

Figure 2 is a schematic circuit diagram of the control circuit of Figure 1; and
Figure 3 is a schematic circuit diagram of an alternative control circuit according to the invention.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

5 Reference is made to Figure 1 where there is illustrated a control circuit 101 for a load in the form of hardware 102 of a laptop computer 103. Circuit 101 includes input terminals 105 and 106 for electrically connecting with respective terminals 107 and 108 of a battery pack 109. The battery pack 109 supplies a battery current and has a predetermined maximum operational current. Circuit 101 also includes output terminals
10 111 and 112 for electrically connecting in parallel hardware 102 and a supercapacitor 113. A controller 115 is disposed between the input and the output terminals for allowing the battery to transfer energy to hardware 102 and supercapacitor 113 while maintaining the battery current at less than the predetermined maximum operational current.

 Supercapacitor 113 provides a smoothing effect for the supply voltage across
15 terminals 111 and 112. That is, the current demand of hardware 102 varies considerably over very short time periods and supercapacitor 113 is able to provide an averaging affect to the battery current. This is achieved due to the low ESR and high capacitance of the supercapacitor. Moreover, supercapacitor 113 is of significantly smaller volume than
20 other supercapacitors. This is particularly significant in portable electronics applications such as those contemplated for the preferred embodiments.

 A supercapacitor for use in the preferred embodiment includes is rated at about 3 Farads, and has dimensions of 150 mm x 180 mm x 1.5 mm. In other embodiments use is made of alternative supercapacitors having different capacities and dimensions. For
25 example, with loads other than laptop computers, such as a PDA, the power requirements and physical size of the load is much smaller, and smaller supercapacitors are used.

 Pack 109 includes a rigid plastic housing that contains a bank of batteries and/or other energy storage devices 117 that are disposed in parallel with a protection circuit 118. As will be appreciated by those skilled in the art, pack 109 is typically removably received
30 within a complementary port (not shown) of computer 103.

 Circuit 118 is connected in parallel with terminals 107 and 108. The function of circuit 118 is to protect batteries 117 from an over-current condition, which is defined as

- 6 -

being a current greater than or equal to the predetermined maximum operational current. This is particularly important for some battery types, such as Li-Ion batteries, where an over-current condition can quickly and easily irreversibly damage the battery and compromise its subsequent performance. In more extreme cases, such conditions render
5 the battery inoperative. Circuit 118 is typically built into the pack 109.

Once circuit 118 detects that the battery current is equal to or greater than the predetermined maximum operational current, it electrically isolates batteries 117 from terminals 107 and 108. Once this occurs, the energy stored within supercapacitor 113 will within seconds quickly drain to a point where the voltage across that supercapacitor will
10 not be sufficient to sustain operation of hardware 102. This has the effect of removing power from hardware 102.

Pack 109 is usually designed such that the over-current condition is not likely to be experienced during normal operating conditions. However, with supercapacitor 113 in parallel with the load, the effective resistance, as seen by the battery, will be very low.
15 Accordingly, if supercapacitor 113 is uncharged or at a low state of charge, the inrush current will typically exceed the predetermined maximum operational current. As supercapacitor 113 will usually be in a low state of charge when a user powers-up hardware 102, circuit 101 will be called into operation at that time.

In other embodiments, circuit 101 is applied to other load such as PDA's, PC
20 cards, Compact Flash cards, and other wireless electronic devices. Circuit 101 is particularly advantageously applied to digital circuits, as these tend to draw peak currents for short periods. That is, the benefits of a high capacitance low ESR supercapacitor are significant, as to is the inclusion of a protection circuit, such as circuit 101, to ensure that currents are maintained within specification without having to redesign or upgrade battery
25 pack 109. This retrofit functionality allows circuit 101 to be easily included within existing products. Moreover, as the preferred supercapacitors are thin – in the order of about 1 mm – it is relatively straightforward to incorporate these components into an existing product to provide superior performance.

In those embodiments where circuit 101 and supercapacitor 113 are, in the first
30 instance, integrally designed with the other components shown, it is possible to combine circuit 101 and circuit 118.

- 7 -

Control circuit 101 is shown in more detail in Figure 2, where corresponding features are denoted by corresponding reference numerals.

It will be appreciated by those skilled in the art that the battery pack has a plurality of batteries and protection circuitry to provide a predetermined maximum operational current for the batteries. That maximum current is typically determined by the type and capacity of the batteries themselves. The intention of the maximum is to prevent the battery pack from supplying a current that would degrade or destroy the batteries.

Circuit 101 includes controller 115 that operates to provide the above functionality. The positive terminal (pin 3) of amplifier U1A is responsive to a reference voltage that is derived from the voltage on one side of shunt resistor R9, the reference being generated by LM385Z2.5 and the surrounding resistor network. The negative terminal of amplifier U1A (pin 2) is responsive to the voltage on the other side of resistor R9. Under normal operating conditions, with battery pack 109 supplying the required current below the predetermined maximum operational current, the output of amplifier U1A will be low (as the voltage at pin 2 is greater than the voltage at pin 3). Hence, M2 will be on, and the voltage at terminal 111 will be only slightly less than the voltage at terminal 105.

The MOSFET switches M1 and M2 are of the type that are used in notebook computer power inputs, although with a number of important variations, as will be discussed below. While use is made, in this embodiment, of two such switches, in other embodiments a different number is used. In other designs, these switches are used as switches only – that is, they are either in an ON state or an OFF state. The switch M2 in this embodiment, however, operates additionally in a linear state between the other two states.

In normal operation, both M1 and M2 are fully ON. That is, when the battery pack is able to supply the total combined current requirements of load 102, supercapacitor 113 and circuit 101. However, when M2 is used to limit the current to the supercapacitor and load – that is, when the combined current load being drawn from battery pack 109 would exceed the predetermined maximum operational current – it is used as a linear control device. It also functions in this way while the supercapacitor is being charged from the battery charger. Due to the resistance provided by M2 in this

- 8 -

third state, it is mounted to a heat-sink that is adequate to allow it to function for the length of time required to effect full charging of the supercapacitor.

In this embodiment, M1 and M2 are RFP60P03 type devices. However, in other embodiments use is made of surface-mount types RF1S60P03. These are P-channel 60
5 Amp 27 m Ω devices, capable of dissipating up to 176 Watts. They also have relatively low gate threshold voltage (-4 Volts maximum). In other embodiments use is made of alternative MOSFETs. In even further embodiments, use is made of bipolar transistors.

The operational amplifiers in circuit 101 have been chosen to accept rail-to-rail input voltages. In this embodiment, use is made of type LM6132 amplifiers. These are
10 high-bandwidth amplifiers that have high input impedance and require low power, making them suitable for use with batteries. They operate from supply voltages from approximately 2.7 Volts to 24 Volts, which is well outside the required range of this circuit.

Note that the differential input voltages of these amplifiers should not exceed 15
15 Volts. It is also preferable that the inputs of an unused amplifier be connected to the same supply rail.

Low-power 2.5 Volt reference voltages for the current limit and low-voltage detection are provided by U3 and U4, which are LM385Z2.5 type amplifiers.

Dual operational amplifiers U1A and U1B take their supply from the left of the
20 shunt resistor, to enable them to control M2. U2A takes its supply from the right of M2, to allow it to turn off M1 completely when the battery voltage is lower than that on the supercapacitor, or when the charger is supplying power.

The shunt resistor is selected such as to drop a suitable voltage when the expected current is passed through it, and its power rating must be sufficient to dissipate the
25 expected RMS power losses resulting from the current. The 30 m Ω shunt used in this embodiment drops 300 mV when a 10 Amp battery current is flowing. This will cause 3 Watts of heat dissipation. The operational amplifiers have an input offset voltage rating of up to 8 mV (maximum). Therefore, there may be an error of up to 267 mA in the current measurement resulting from the input offset current. However, as the battery current
30 reaches about 7 Amps to 10 Amps, this amount of error is acceptable. In other applications use is made of operational amplifiers with lower offset currents to reduce the current error referred to above.

- 9 -

The current-limit function is performed by U1A. It compares the voltage drop across the shunt with the divided value of the reference voltage. It operates when the current is flowing from left to right in Figure 2, so the shunt voltage is positive on the left, which is what happens when the supercapacitor is being charged. If the current exceeds the reference value for a time determined by its RC time constant, its output swings high to turn off M2. In this embodiment, capacitor C4 and resistor R8 determine the time constant. If the time constant is short enough, as is the case in this embodiment, the control is smooth and linear. Some caution is required, for if a long time constant is used, the control output may become oscillatory. In those embodiments where fast control is critical, C4 has a low value, while in further embodiments, C4 is omitted. It will be appreciated by those skilled in the art that this time constant is altered to suit the application.

Having a non-zero time constant means that the circuit will not react instantly to current pulses that exceed the predetermined maximum operations current that is set by the reference input. This provides some immunity to high current pulses that are short enough not to be of concern. The maximum current, though, is set high enough to support the maximum short-term average current the load draws in normal operation, otherwise the current limit will operate, causing the voltage to drop and the system to malfunction.

That is, batteries 117 are able to accommodate, without sustaining damage, pulse loads where over-current conditions exist. However, this on the proviso that that load has a short duration. Typically, protection circuit 118 is configured to allow higher currents to flow for a predetermined time, where that time is dependent upon the magnitude of the current.

The magnitude of the predetermined maximum operational current is set by the potentiometer R12. The greater the voltage across C7, the greater will be the current before U1A begins to turn off M2. In other embodiments, R12 is substituted by two equivalent but discrete resistors, both with approximately the same total resistance.

Circuit 101 also includes a low-voltage lockout circuit 121 that is centred about operational amplifier U1B. More particularly, amplifier U1B is used as a comparator, and performs the low-voltage lockout or shut-down function. The battery and charger voltages are applied via Schottky diodes to a potentiometer R1. In other embodiments the potentiometer is replaced with resistors. The higher voltage of the respective

- 10 -

voltages provided by the battery and the charger is used to determine whether to turn off M2. If the higher of these two voltages is lower than the reference at pin 5 of U1B by an amount modified by a hysteresis feedback resistor R15, the output of U1B goes high, turning off M2.

5 The higher of the two voltages applied to pin 6 of U1B has to increase beyond the original value before M2 will be turned on again. This prevents rapid spurious switching during transients. In those embodiments where an increased hysteresis effect is required, R15 is reduced in value. Conversely, in those embodiments where a reduced hysteresis effect is required, R15 is increased in value.

10 Capacitor C13 filters the voltages applied to pin 6 of U1B. The greater the value of C13, the larger the effective time-constant of C13 and the combination of R17 and R11 will be. In turn, the longer the time constant, the longer the circuit will take to respond to a voltage drop below the pre-set level. The filtering therefore helps to prevent unnecessary shutdowns caused by short transients in voltage.

15 Circuit 101 also includes a reverse current detection circuit 122 that is based around U2A. This circuit 122 allows protection of the batteries from reverse current. To provide this functionality, U2A is also used as a comparator. It turns off M1 when the voltage on supercapacitor 113 and load 102 is greater than that provided by battery pack 109. It also turns off M1 when the voltage on the charger input is high enough to power the circuit. The charger's power input is monitored via Schottky diode D8. Because this diode carries very little current, the cathode of D8 will be at a higher voltage than the cathode of the device's existing input power diode when power is being supplied by the charger. Either a high supercapacitor voltage or a high charger voltage causes U2A to switch its output high.

25 The theoretical value of the current limit provided by circuit 115 is determined from the shunt resistor's value and the voltage drop across C7 (across the upper part of the potentiometer/resistor divider). The current at which limiting begins is:

$$I_{lim} = V_{C7}/R_9.$$

The likely error in this value is determined mainly by the offset voltage of the operational amplifier.

30 In cases where the circuit of Figure 2 is retrofitted to a laptop computer the actual value of the current limit is best confirmed by measurement. This includes connecting a

battery or power supply to the battery input, then noting the value at which the current limits when a load (or short-circuit) is applied to the supercapacitor (load) terminals. The current should be just below the continuous value that will cause the battery to shut down. In other embodiments where the circuit of Figure 2 is designed as an integrated component, the relevant values would be known.

The value of the time constant in the current limit circuit is determined by $R8 \times C4$. $C4$ is, in some embodiments, omitted for fast response. In those cases where this omission causes limiting in normal operation because of fast transient currents, then a value of $C4$ is added that is sufficient to prevent limiting during very short transients. The size of $C4$ is determined analytically, and is preferably as small as it can possibly be without the limiting occurring.

When a discharged supercapacitor is connected to the supercapacitor terminals and the battery is connected to its terminals, the current limits to the desired value without being sufficient to cause the circuit 109 to shut down further battery current. $C4$ is small enough that the limiting acts quickly, preventing battery shutdown. This allows the supercapacitor to charge or recharge as quickly as possible without causing premature shut down of the laptop.

The reference voltage used by the circuit of Figure 2 to determine a cutoff voltage is determined by the component LM385Z2.5. Once the desired cutoff voltage is known, the resistor values substituted for $R11$ are determined as follows.

1. If there is no hysteresis ($R15$ is absent), then the divided value of the supply presented to pin 6 of $U1B$ is equal to 2.5 Volts, the reference voltage.
2. With hysteresis this value is reduced slightly by approximately $(2.5 \times R16)/(R16+R15)$, the hysteresis voltage.

With the values in the circuit, there is approximately a 1% hysteresis, or 25 mV. Allowance is made for the offset voltage of the amplifier, which is 8 mV (maximum).

The time constant of the low-voltage cutoff is determined by $R11$, $R17$ and $C13$. In other embodiments, $R11$ is effectively the parallel combination of the two resistors that replace the one shown. The total value of this equivalent resistor plus $R17$ is then multiplied by $C13$. This time constant is selected to be approximately the desired response time to short-term voltage drops. If it is less than this time, then the circuit will tend to shut down the supply to the load during such voltage drops.

- 12 -

This circuit also allows for customisation of the hysteresis in the reverse-current protection circuit. This value is determined from the ratio $R2/(R1+R2)$ for the supercapacitor's voltage, or $R4/(R1+R4)$ for the battery charger input. The ultimate value needs to be large enough to prevent the circuit from turning off M1 unnecessarily during voltage transients, but not so large that the supercapacitor/load voltage has to drop very much before the battery is re-connected.

It has been found during the development of the preferred embodiment that high ripple currents in notebooks and other portable electronic and computing devices is drastically reduced by the use of a supercapacitor in parallel with the supply. The reduction in the magnitude of ripple currents provides:

1. A reduced risk of premature shutdown
2. Improved efficiency, especially with reduced battery voltages
3. Small increases in battery run-time
4. Increased battery life due to reduced current peaks.

However, a supercapacitor needs to be charged on power-up. Accordingly the current-limiting charging circuit with low-voltage lockout and reverse-current protection, such as that illustrated in Figure 2, is used in portable devices to prevent the needless switching of the batteries and the consequent shut down of the device.

The circuit of Figure 2 also performs the power-selection function, routing power from the battery or the charger/adaptor, if connected. It has low current drain, which makes it suitable for use in battery-powered devices. As described above, the circuit is open to be tailored to suit different batteries and loads. Moreover, it uses some of the components already present in most notebook computers for the power-selection function.

The CPUs and other devices in notebook computers draw high currents that vary enormously. These generate high levels of voltage ripple in the supply. Placing a very low-ESR supercapacitor in parallel with the DC power input reduces the voltage ripple by a factor of 7 to 10 times, and reduces the battery current peaks by a comparable amount.

Reducing the voltage ripple enables designers to reduce the voltage margin before the system shuts down, without the risk that a voltage droop caused by a current peak will crash the system. This yields additional run-time, by using energy remaining in the battery. It also provides opportunities to improve the efficiencies in the downstream DC-DC converters, particularly if a reduced battery voltage is used.

- 13 -

(Reduced voltage results in reduced current peaks in the circuit board traces, inductors and decoupling capacitors, which gives reduced I^2R losses.) The reduced current peaks demanded from the battery also extend battery life.

5 It is necessary to charge the supercapacitor to the supply voltage when the system is turned ON. If it were connected directly to the battery or the charger, the current drawn would be very high. Therefore, it is necessary to limit the charging current until the supercapacitor is charged.

10 The supercapacitor has a voltage rating that must not be exceeded. Therefore, it is necessary that any charger that is used does not charge the supercapacitor to a higher voltage than this rating.

If a battery is inserted that has a lower voltage than that on the supercapacitor, it is necessary to prevent a large current flowing from the supercapacitor into the battery. It is usual for the supercapacitor voltage to be higher than the battery voltage if the load was previously powered by a battery-charger. Another situation where this voltage
15 condition occurs is when a fresh battery had been in use, and it was quickly removed and replaced with a near-depleted battery. That is, if the system is drawing very little power, the supercapacitor will, in all likelihood, not have discharged sufficiently in the time it takes to insert the other battery.

20 When the battery's voltage drops to a low level, it is necessary to shut down the supply to the device, to prevent possible damage to the battery. This low-voltage lockout should also operate if the system is being powered by the battery-charger. That is, the presence of a low voltage suggests there is a fault in the charger or load. Also, the load – that is the laptop – will not function correctly when the voltage is low, because part or all of it will shut down.

25 The circuit of Figure 2 is for a notebook computer, but other embodiments are used in power supply circuits for other portable devices. The circuit limits the battery current to the supercapacitor and the system while the supercapacitor is charging.

30 The circuit has reverse-current protection that prevents large currents flowing from the supercapacitor to the battery. It does this by detecting when the voltage on the supercapacitor is higher than that of the battery. Since the conduction path between the supercapacitor and the battery has low impedance, there is necessarily a small current flowing in that direction before the voltage difference is large enough to cause the circuit

- 14 -

to activate. However, this current is small and will not be enough to damage the batteries or activate any of the battery protection circuitry.

The circuit also has a low-voltage lockout function that cuts off the load when the supply voltage drops below a pre-determined level.

5 The circuit for the battery-charger is not covered, but it will be understood that it connects to the battery, in use, via a charging circuit that is not shown in the Figure. The battery-charger should not be permitted to supply more than the rated voltage to the supercapacitor used on the internal DC supply. In one embodiment this is achieved by adding a simple linear voltage regulator to the output from a standard regulator. Another
10 embodiment includes a modification to the circuit of the battery-charger so that its output is the correct voltage. The latter minimises the heat generated by the charger's circuit.

An alternative embodiment of the invention, in the form of a control circuit 130, is shown in Figure 3. It will be appreciated that corresponding features are denoted by corresponding reference numerals. Circuit 130 is used as a substitute for circuit 101 in
15 Figure 1, where the application demands.

Circuit 130 includes a controller 131 that is based around U1 of Figure 3. This operational amplifier is configured as a comparator and compares a reference voltage – that is provided by D1 and the associated resistors – with the voltage on the opposite terminal of a shunt resistor R1. The output of U1 (pin 1) drives M1 (pin 4) into an ON
20 mode or an OFF mode. This is similar to operation of circuit 115 of Figure 2, as U1 is also set up to drive M1 in a linear mode.

When the output of U1 is high – due to too much current flowing in R1 – M1 is off and battery pack 109 is effectively electrically isolated from load 102 and supercapacitor 113. In normal operating conditions, the output of U1 is low, and M1 is ON to allow the
25 battery pack 109 to supply the battery current to load 102 and supercapacitor 113. When the battery current approaches the predetermined maximum operational current, U1 drives M1 to vary its resistance so that the battery current is maintained below the predetermined maximum.

At start up, it takes some time for U1 to become operational. However, capacitor
30 C2, in addition to providing a hysteresis effect for U1, also ensures that, at start up, pins 4, 5 and 8 of M1 are maintained at a similar voltage. The small value of C2 ensures that M1 is, after a very small initial delay, switched OFF. During that initial delay there will be a

- 15 -

small peak of battery current. As this current is allowed to flow for only a short period – due to the small size of C2 – the risk of triggering circuit 118 is low.

Circuit 130 also includes an enable circuit 132 having an external input 133. In the event input 133 is held low or left floating circuit 132 is inactive and has no effect.

- 5 However, when input 133 is held high, it disables circuit 130 by turning M1 OFF. For example, in some embodiments, terminals 111 and 112 supply power to a load that is a wireless transmitter (not shown) that has both control circuitry and transmission circuitry. Typically, it is the latter that consumes substantially more peak power and it is not powered up until the control circuitry has conducted pre-processing and set-up routines.
- 10 The control circuitry is connected with input 133, and holds this high while the set-up routines are run. Once these have come to a satisfactory conclusion, the control circuitry takes input 133 low to enable circuit 130 to supply power to the transmission circuitry.

While circuit 130 is a general purpose circuit, it has particular application to PC cards or CompactFlash cards.

- 15 Supercapacitor 113 includes two supercapacitive cells (not shown) that are connected in series in a single package 134. Extending from the package is a positive terminal 135 that is connected to terminal 111 and a negative terminal 136 that is connected to terminal 112. A third terminal 137 extends from the junction of the two cells and is connected to the junction of resistors R9 and R10. Those resistors define a resistive
- 20 balance to ensure that the cells are maintained at substantially equal voltages.

Although the invention has been described with reference to specific examples, it will be appreciated by those skilled in the art that it may be embodied in many other forms.

CLAIMS

1. A control circuit for a load, the circuit including:
input terminals for electrically connecting with respective terminals of a battery
that has a predetermined maximum operational current whereby the battery supplies a
5 battery current;
output terminals for electrically connecting in parallel the load and a
supercapacitor; and
a controller being disposed between the input and the output terminals for allowing
the battery to transfer energy to the load and the supercapacitor while maintaining the
10 battery current at less than the predetermined maximum operational current.
2. A circuit according to claim 1 wherein the controller also prevents the
supercapacitor from providing energy to the battery.
3. A circuit according to claim 1 that is a power-up protection circuit for a portable
computing device.
- 15 4. A circuit according to claim 1 wherein the load draws a load current that varies
with time, where the load current is the sum of the battery current and the current provided
by the supercapacitor.
5. A circuit according to claim 4 wherein the load current is greater than or equal to
zero and the controller maintains the battery current at greater or equal to zero.
- 20 6. A circuit according to claim 1 wherein the predetermined maximum operational
current is an average over a given interval.
7. A circuit according to claim 1 wherein the predetermined maximum operational
current is an instantaneous current.
8. A circuit according to claim 1 wherein the battery includes a plurality of battery
25 cells.
9. A circuit according to claim 1 wherein the battery includes a protection circuit
for electrically disconnecting the battery terminals from the input terminals in response
to the predetermined maximum operation current being exceeded.
10. A circuit according to claim 1 wherein the controller is responsive to the battery
- 30 current for varying a resistance between the input and the output terminals.
11. A circuit according to claim 10 wherein the controller includes one or more solid-
state devices for varying the resistance.

- 17 -

12. A circuit according to claim 11 wherein at least one of the solid-state devices is a MOSFET.
13. A circuit according to claim 11 wherein the load has a start up sequence and the at least one of the solid-state devices operates in a linear mode during that sequence.
- 5 14. A circuit according to claim 11 wherein the at least one solid state device is mounted to a heat sink.
- 15 A control circuit for a load, the circuit including:
input terminals for electrically connecting with respective terminals of a battery that has a predetermined maximum operational current whereby the battery supplies a
10 battery current;
output terminals for electrically connecting in parallel the load and a supercapacitor; and
a solid state device through which the battery current flows between the input and the output terminals, the transistor being responsive to the battery current for varying the
15 resistance of the transistor and thereby allowing the battery to transfer energy to the load while maintaining the battery current at less than the predetermined maximum operational current.
16. A circuit according to claim 15 wherein the solid state device is a transistor.
17. A circuit according to claim 16 wherein the transistor is a MOSFET.
- 20 18. A circuit according to claim 17 wherein the MOSFET is mounted to a heat sink.
19. A control circuit for a computing device that derives power from a battery unit that has a battery and a protection circuit for isolating the battery from the device when predetermined maximum operational current is exceeded, the control circuit including:
input terminals for electrically connecting with respective terminals of the
25 protection circuit to allow the battery to supply a battery current to the device;
output terminals for electrically connecting in parallel the load and a supercapacitor; and
a controller being disposed between the input and the output terminals for allowing the battery to transfer energy to the load and the supercapacitor while maintaining the
30 battery current at less than the predetermined maximum operational current.
20. A portable computing device including:

- 18 -

a power source having at least two output terminals for supplying a source current of up to a predetermined maximum operational current;

computer hardware that includes a supply rail that draws a load current;

a supercapacitor in parallel with the supply rail; and

5 a controller being disposed between the output terminals and the supply rail for allowing the source to transfer energy to the hardware and the supercapacitor while maintaining the source current at less than the predetermined maximum operational current.

21. A control circuit for a load, the circuit including:

10 input terminals for electrically connecting with respective terminals of a battery that supplies a battery current, wherein the battery has a predetermined maximum operational current and a predetermined pulse current capacity;

output terminals for electrically connecting in parallel the load and a supercapacitor; and

15 a controller being disposed between the input and the output terminals for allowing the battery to transfer energy to the load and the supercapacitor while controlling the battery current such that the battery remains within the predetermined pulse current capacity.

22. A circuit according to claim 21 wherein the controller provides a current path for 20 the battery current between the input and the output terminals and is responsive to both the quantum and the duration of the battery current for varying the resistance of the path.

23. A circuit according to claim 22 wherein the resistance of the path is varied once the predetermined pulse current capacitor has been reached.

24. A circuit according to claim 23 wherein the resistance of the path is varied to 25 maintain battery current below the predetermined maximum operation current.


- 19 -

ABSTRACT

A control circuit (101) is configured for use with a load in the form of hardware (102) of a laptop computer (103). Circuit (101) includes input terminals (105, 106) for electrically connecting with respective terminals (107, 108) of a battery pack (109). The
5 battery pack (109) supplies a battery current and has a predetermined maximum operational current. Circuit (101) also includes output terminals (111, 112) for electrically connecting in parallel hardware (102) and a supercapacitor (113). A controller (115) is disposed between the input and the output terminals for allowing the battery to transfer energy to hardware (102) and supercapacitor (113) while maintaining
10 the battery current at less than the predetermined maximum operational current.

- 1/3 -

FIGURE 1



- 2/3 -




FIGURE 2




FIGURE 3

Box No. VIII (iv) DECLARATION: INVENTORSHIP (only for the purposes of the designation of the United States of America)
The declaration must conform to the standardized wording provided for in Section 214; see Notes to Boxes Nos. VIII, VIII (i) to (v) (in general) and the specific Notes to Box No. VIII (iv). If this Box is not used, this sheet should not be included in the request.

Declaration of inventorship (Rules 4.17(iv) and 51 bis.1(a)(iv)) for the purposes of the designation of the United States of America:

I hereby declare that I believe I am the original, first and sole (if only one inventor is listed below) or joint (if more than one inventor is listed below) inventor of the subject matter which is claimed and for which a patent is sought.

This declaration is directed to the international application of which it forms a part (if filing declaration with application).

This declaration is directed to international application No. PCT/AU03/01117 (if furnishing declaration pursuant to Rule 26ter).

I hereby declare that my residence, mailing address, and citizenship are as stated next to my name.

I hereby state that I have reviewed and understand the contents of the above-identified international application, including the claims of said application. I have identified in the request of said application, in compliance with PCT Rule 4.10, any claim to foreign priority, and I have identified below, under the heading "Prior Applications," by application number, country or Member of the World Trade Organization, day, month and year of filing, any application for a patent or inventor's certificate filed in a country other than the United States of America, including any PCT international application designating at least one country other than the United States of America, having a filing date before that of the application on which foreign priority is claimed.

Prior Applications:

I hereby acknowledge the duty to disclose information that is known by me to be material to patentability as defined by 37C.F.R. § 1.56, including for continuation-in-part applications, material information which became available between the filing date of the prior application and the PCT international filing date of the continuation-in-part application.


I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

Name: Pierre MARS

Residence: New South Wales, Australia
 (city and either US state, if applicable, or country)

Mailing Address: Units 9 & 10, 12 Mars Road, Lane Cove, New South Wales 2066, Australia

Citizenship: Australian

Inventor's Signature: 
 (if not contained in the request, or if declaration is corrected or added under Rule 26ter after the filing of the international application. The signature must be that of the inventor, not that of the agent)


Date: 25/09/03
 (of signature which is not contained in the request, or of the declaration that is corrected or added under Rule 26ter after the filing of the international application)

Name: George Lange PAUL

Residence: New South Wales, Australia
 (city and either US state, if applicable, or country)

Mailing Address: 21A Greville Street, Chatswood West, New South Wales 2067, Australia

Citizenship: Australia

Inventor's Signature: 
 (if not contained in the request, or if declaration is corrected or added under Rule 26ter after the filing of the international application. The signature must be that of the inventor, not that of the agent)

Date: 25/09/03
 (of signature which is not contained in the request, or of the declaration that is corrected or added under Rule 26ter after the filing of the international application)



This declaration is continued on the following sheet, "Continuation of Box No. VIII (iv)".

**This Page is Inserted by IFW Indexing and Scanning
Operations and is not part of the Official Record**

BEST AVAILABLE IMAGES

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images include but are not limited to the items checked:

- ☐ BLACK BORDERS
- ☐ IMAGE CUT OFF AT TOP, BOTTOM OR SIDES
- ☐ FADED TEXT OR DRAWING
- ☐ BLURRED OR ILLEGIBLE TEXT OR DRAWING
- ☐ SKEWED/SLANTED IMAGES
- ☐ COLOR OR BLACK AND WHITE PHOTOGRAPHS
- ☐ GRAY SCALE DOCUMENTS
- ☒ LINES OR MARKS ON ORIGINAL DOCUMENT
- ☐ REFERENCE(S) OR EXHIBIT(S) SUBMITTED ARE POOR QUALITY
- ☐ OTHER: _____

IMAGES ARE BEST AVAILABLE COPY.

As rescanning these documents will not correct the image problems checked, please do not report these problems to the IFW Image Problem Mailbox.